PR104225: CHHA CASA GRANDE DEVELOPMENT



<u>DESCRIPTION</u>: Furnish all required labor, materials and equipment necessary to provide Scope-of-Service at the described location. Work is being authorized under the elected TML TurnKey Recovery Program<sup>sM</sup> administered by SynergyNDS on behalf of Cameron County Housing Authority, a Member of Texas Municipal League Intergovernmental Risk Pool (TMLIRP).

**LOCATION:** Casa Grande Development | 29ea Single Family Affordable Housing 104 Troywood Circle | Harlingen, Texas 78552

**SUBMITTAL INSTRUCTIONS:** For purposes of generating bid - IFB Packet includes scope specifications and bid sheet specific to referenced project.

- Bids shall be received no later than 07/25/19 (emailed to bids@synergynds.com)
- All registered HUB Contractors (through the Texas Comptroller's Office), as well as DBEs are encouraged to participate. Additional <u>Contractor Financial Assistance</u> is available to help support daily HUB/DBE Contractor's Operations under terms and condition of successful contract award.
- Contractor is required to identify and validate all necessary task items, measurements/dimensions &/or other applicable conditions in support of described scope-of-work. Contractor's Bid is to account for all work to be performed in accordance to trade standards and as required by Ordinance & Law (whether or not a 3<sup>rd</sup> Party Professional has provided additional comment/support material).
- Bid shall be completed and submitted using **ONLY** the **Contractor Submittal Form** (provided at the end of the IFB Packet).
- Bid award will be made based on best overall LUMP SUM project value as determined by SynergyNDS in accordance to market valuation, project demands, critical path scheduling as well as overall HUD Participation Goals. Contributing factors, in addition to price, may be considered as necessary to help determine bid award based on any additional criteria set forth by the specific TMLIRP Insured Member.
- Bids received after above deadline or that are not submitted in accordance to Submittal Instructions may be rejected without further explanation or contractor notification.

### **RETURN BID TO: SynergyNDS / TML**

TML Turnkey Recovery Program Attention: <a href="mailto:bids@synergynds.com">bids@synergynds.com</a>
Request On-Site Project Visit by emailing bids@synergynds.com

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

**SCOPE OF WORK:** The Casa Grande Development is comprised of a total of 65 Single Family Homes consisting of 2/3/4 Bedroom Models. To date, 29 Units have been impacted by Flood Damage as identified in the IFB. Units average 1153 SF (Finished Space) with an estimated Unit Total at 33,450 SF (Refer to the Attached Appendix Section).

Scope includes labor, tools, equipment, installation, PPE, materials, supervision, and insurance necessary to complete the work described in general below. All scope-of-work shall be completed in accordance to manufacture specifications, building codes and applicable industry standards. Work is to begin no later than 3 days from contract award notification. Any concerns with timeline is to be discussed with onsite project manager and an email is to be sent to <a href="mailto:admin@synergynds.com">admin@synergynds.com</a> for contract documentation.

Scope shall include all work governed by industry Best Practices & Standards whether specifically identified in the IFB. The <u>Closed Method Structural Drying & Decontamination Cleaning</u> approach could include the necessary usage of desiccant drying systems, air movers and low grain refrigerant (LGR) dehumidification systems to provide for structural drying and controlled environmental conditions at the start of the Stabilization & Mitigation project. SEE THE ATTACHED APPENDIX D FOR THE CALCULATED NUMBER OF EQUIPMENT TO ACHIEVE THE PROPER DRYING CAPACITY PER HOUSING UNIT.

Contractor is responsible to determine and provide all necessary &/or required PPE (personal protective equipment) in accordance to Industry Standards (OSHA, ICCRC or etc) for any personnel performing work under their specific IFB contract award.

#### **DETAILED AND FINAL DECONTAMINATION CLEANING**

FINAL PHASE CLEANING AND DISINFECTION PROCEDURES - ALL UNITS

\*\*ALL DISINFECTION WILL UTILIZE AN APPROVED DISINFECTANT FOR ALL FLOOD IMPACTED LOCATIONS THAT WILL REQUIRE POST RESTORATION VERIFICATION TESTING\*\*\*

<u>WALL SYSTEM FRAMING AND SHEATHING (PLYWOOD AND GYPSUM BOARD)</u> – Exterior and Interior Walls After the flood water impacted materials are removed and the gross cleaning of the structure is completed, then the structural surface cleaning and washing can begin to a level where post restoration verification (PRV) testing and assessment will pass. The following outlines the general procedures in order to properly accomplish the decontamination cleaning of the remaining structure.

- ➤ The exposed and remaining wood wall stud framing (interior and exterior wall systems) and exterior wall sheathing shall be HEPA vacuumed completely. This also includes base plates and framing around doors and windows.
- > The HEPA vacuumed stud wall interior and exterior framing and exterior sheathing surfaces shall be physically cleaned using wet cleaning or wash methods with a detergent solution.

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

- ➤ The cleaning or detergent solution should be applied with a sprayer, then physically cleaned using a stiff nylon brush designed for scrubbing of the stud wall interior and exterior framing and exterior sheathing surfaces.
- ➤ The scrubbed clean stud wall interior and exterior framing and exterior sheathing surfaces shall then be wiped clean with a microfiber cloth, rag or equivalent to remove any residual detergent solution, surface dust, demo debris or contamination.
- The cleaned stud wall interior and exterior framing and exterior sheathing surfaces shall be disinfected by a disinfection application with EPA registration approved for environmental application suitable to kill environmental bacteria and fungi.
- ➤ The disinfection process shall include application via pump sprayer, mister or pressure sprayer or equivalent to ensure bio-washing is distributed and applied uniformly and generously. This is performed to establish adequate wet coverage for 10 continuous minutes or per the product labeling.
- > The disinfected stud wall interior and exterior framing and exterior sheathing surfaces are then allowed to air dry for 10 minutes for adequate Category 3 black water microbial kill.
- This process may be duplicated until the structure is sufficiently cleaned, disinfected and decontaminated.

<u>CONCRETE SUBFLOORING:</u> The exposed concrete slab shall be surface cleaned and washed to a level where post restoration verification (PRV) testing and assessment will pass. The following outlines the general procedures in order to properly accomplish the decontamination cleaning of the remaining subfloor structure.

- > The exposed and remaining concrete subflooring and non-removed ceramic floor tile materials shall be HEPA vacuumed completely.
- The HEPA vacuumed concrete subflooring and non-removed ceramic floor tile surfaces shall be physically cleaned using wet cleaning or wash methods with a detergent solution.
- ➤ The cleaning or detergent solution should be applied with a sprayer, then physically cleaned using a stiff nylon brush designed for scrubbing of the concrete subflooring and non-removed ceramic floor tile surfaces.
- The scrubbed clean concrete subflooring and non-removed ceramic floor tile surfaces shall then be wiped clean with a microfiber cloth, rag or equivalent to remove any residual detergent solution, surface dust, demo debris or contamination.
- The cleaned stud concrete subflooring and non-removed ceramic floor tile surfaces shall be disinfected by a disinfection application with EPA registration approved for environmental application suitable to kill environmental bacteria and fungi.

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

- The disinfection process shall include application via pump sprayer, mister or pressure sprayer or equivalent to ensure bio-washing is distributed and applied uniformly and generously. This is performed to establish adequate wet coverage for 10 continuous minutes or per the product labeling.
- ➤ The disinfected concrete subflooring and non-removed ceramic floor tile surfaces are then allowed to air dry for 10 minutes for adequate Category 3 black water microbial kill.

### STRUCTURAL DRYING (CLOSED DRYING METHOD)

STRUCTURAL DRYING PROCEDURES - ALL UNITS - CLOSED DRYING METHOD

#### CLOSED METHOD STRUCTURAL DRYING MEANS AND METHODS (All Units)

Directed heat drying and dehumidification (using desiccant drying or air movers and LGR portable systems) will be utilized in select locations of each of the 29 affected housing units where the moisture content of the exterior building envelope sheathing, exterior wall framing, interior wall framing, and related structural framing building materials is elevated beyond 18%. This includes the wood framing and exterior sheathing materials and interior wood wall framing materials. Once the elevated moisture is removed from the wood wall framing and sheathing building materials (less than adjusted 18% moisture content, per the ANSI / IICRC \$500 Standard) and controlled, the directed heat drying and dehumidification will be reduced or strategically removed appropriately until the drying process is successful and completed.


FOR DISCUSSION PURPOSES: Contractor should be prepared to account for a per Unit drying cycle of a minimum of 5-days given the water wicking/saturation of structure, nature of the flood loss and humidity conditions of non-climate controlled indoor space. It is Contractor's responsibility to determine the proper Drying Equipment usage and quantities as necessary to promote effective stabilization services in order to prepare for IH Clearance Sampling.

Based on the overall average Unit Sizes of approximately 1153 SF and various Unit Model Layouts, it is reasonable to assume the following:

- Units will need a minimum three (3) LGR dehumidification units with a minimum total capacity of 250 pints per day.
- Units will need a minimum of 15 air movers directed along the perimeter walls and interior walls in order to properly dry out the wood frame structure and sheathing that was water impacted to a maximum of adjusted 18% moisture content.
- o It is recommended that (2)ea Air Scrubbers be utilized in each Unit as necessary to achieve a successful air-changeover rate in order to prepare for IH Indoor Clearance Sampling.
- The directed heat process to dry out the wood framed structure includes the following process.

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

- ✓ Turn on unit HVAC system and place the system in heat mode between 80-85 degrees. Make sure the T-stat is in "FAN ON" mode at all times.
- ✓ Construct drying chambers or focused drying zones consisting of 6 mil polyethylene sheeting taped or fastened at the 5 ft mark on demoed wall and extend poly sheeting to the floor approximately 3 ft from the base plate to construct a small, triangle shaped drying chamber with loose end caps to allow for entry air for drying and exhaust air out of the drying chamber. Refer to Diagram Below:



- ✓ Place an air mover in drying chamber every 10 linear ft and angle the air mover (30-45 degrees) towards the target wall materials to dry.
- ✓ Place one LGR dehumidification unit at one end of the drying chamber and orient the discharge end of the LGR unit into the drying chamber to push hot, dry air into the drying chamber for the air movers to continue to push drying air around the structure.
- ✓ The closed drying method to dry the wood framing and sheathing materials shall be dried to a moisture content of less than the adjusted normal expected building conditions of 18%

#### **RESTORATION CONTRACTOR GENERAL CONDITIONS:**

• The drying equipment, desiccant systems, air movers, low grain refrigerant (LGR) dehumidifiers and HEPA-filtered exhaust units will be installed in such a manner to not interfere with the access into the immediate work area. It is necessary to perform the mathematical calculations to confirm and determine the size and number of equipment to implement on the restoration project. This will also assist in legitimizing the equipment used and billing for the equipment. Electrical power to the equipment shall be GCFI protected.

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

- The containment and HEPA-filtered exhaust units will remain in place and operational until clearance sampling has been completed and results indicate satisfactory completion of restoration work.
- The contractor shall abide by all applicable federal, state, and local regulations and codes and building owner policies. The restoration contractor will use appropriate means and methods consistent with the ANSI / IICRC S500, ANSI / IICRC S520, US EPA and CDC guidelines for flood restoration and remediation.
- The contractor shall protect all unaffected wall finishes, floor finishes, electrical systems, mechanical systems, communication systems, life safety systems, security systems, HVAC control systems, plumbing systems, lighting systems, structurally related components, etc., from damage as a result of the restoration project.
- The contractor shall be responsible for field verifying all conditions prior to implementation of this scope of work.
- The contractor shall be responsible for securing the flood affected areas from access by non-authorized building occupants, including facility staff not directly part of the restoration efforts.
- The contractor shall provide Material Safety Data Sheets (MSDS) to the industrial hygienist of record (IHC, Corp.) for chemical-based products that will be used including, but not limited to, glues, cleaners, solvents, anti-microbial products, sanitizing agents, etc.
- The contractor is responsible to assure that any sub-contractors comply with the provisions of this scope of work.
- The contractor is responsible for inspecting, monitoring and maintaining any containment or minicontainment and critical barrier integrity and exhaust unit performance. This is to ensure the flood affected areas do not compromise the unaffected areas of the property if applicable.
- The contractor is NOT responsible for any conditions or activities the building owner or employees
  implemented prior to their arrival to the job site. This includes removal of contents, equipment or
  personnel from the affected areas to the non-affected areas of the building.
- During the restoration structural drying and decontamination cleaning work, pre-existing damage to the building, building system failures, etc. may be found. If this occurs, the restoration contractor will identify, document and record these deficiencies for review and consideration. The item shall be described, the location of the item shall be noted, the date the item was discovered and why the item was discovered. The restoration contractor shall notify the Recovery Project Manager, Kris Hawk by cell phone (513) 382-0301, of any additional discoveries.

PR104225: CHHA CASA GRANDE DEVELOPMENT

### **GENERAL TERMS & CONDITIONS (Not otherwise specified under SUBMITTALS)**

- Contractor is to obtain their own permits. Permits can be obtained by contacting the Building Department or other administering entity. Permit Fees are reimbursable direct from SynergyNDS (in addition to contractor's Lump Sum Proposal) if incurred and with proper documentation.
- Contractor is to abide by all applicable OSHA requirements and standards. Contractor shall require all employees to utilize proper PPE, including but not limited to: fall protection harnesses, hard hats, safety glasses, safety foot wear, and gloves.
- Contractor may be asked to provide Material Safety Data Sheets (MSDS) to the industrial hygienist of record (IHC, Corp.) for chemical-based products that will be used including, but not limited to, glues, cleaners, solvents, anti-microbial products, sanitizing agents, etc. The industrial hygienist of record retains the right to not allow the use of any of the products selected.
- Contractor shall be responsible for supplying any and all necessary equipment, tools and materials to complete the scope of work unless directed otherwise in the IFB. This includes but is not limited to: Rental Equipment, Dumpsters, Storage Containers, Jobsite Trailer, General Conditions, Associated Expenses, Overhead & Profit which are to be included in the IFB Contractor Lump Sum Proposal.
- Contractor shall keep the Project Site and the surrounding areas free from the accumulation of waste materials, debris, etc. caused by operations performed under this Scope of Work. Upon completion, the contractor shall remove from Project Site, and surrounding areas:
  - Any waste materials, debris, etc. caused by completing the outlined Scope of Work.
  - Any tools, cleaning equipment, machinery, surplus materials originally furnished by the contractor
- The contractor shall be responsible for field verifying all conditions prior to implementation of the scope of work outside of any additional 3<sup>rd</sup> Party Professional assessment.
- The contractor shall provide and implement a site-specific health and safety plan to include hazard communication and related OSHA.
- The contractor is responsible to ensure that any sub-contractors comply with the provisions and terms of this scope of work.
- The contractor is responsible for submitting applicable project and associated contract documents as
  defined by Architectural Drawings Specifications, Engineering Requirements, Certificates of Insurance,
  Change Order Requests and any written or documented deviations from approved scopes-of-work or
  Contract.
- If the contractor determines that deviations, modifications (change order or supplemental costs) from the initial scope-or-work are required, the Contractor shall submit a written request to SynergyNDS for

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

review and approval prior to start of any additional work not otherwise included in initial BID. The written request will contain, at a minimum:

- Reason for deviation or modification
- Description of deviation or modification
- Estimated time required for deviation or modification
- o Project cost addition or subtraction for deviation or modification
- The contractor is NOT responsible for any conditions or activities the building owner or employees implemented prior to their arrival to the job site. This includes removal of contents, equipment or personnel from the affected areas to the non-affected areas of the building.
- During the cleaning work, pre-existing damage to the building, building system failures, etc. may be
  found. If this occurs, the contractor will identify, document and record these deficiencies for review
  and consideration. The item shall be described, the location of the item shall be noted, the date the
  item was discovered and why the item was discovered. The contractor shall notify the Project
  Manager of any additional discoveries.

<u>PAYMENT</u>: Project is managed by SynergyNDS, Inc., under the TML Turnkey Recovery Direct Repair Program. Payment will be made directly from the Turnkey Recovery Managed Direct Repair Program to the contractor(s) in accordance with described terms & conditions. Qualified contractors may be eligible for an upfront material deposit or progress payments as determined prior to BID AWARD. Contractor must be registered in the MVP (Managed Vendor Program) whereby required contractor documents must be uploaded to the database. There is annual \$49.95 processing fee as part of the initial contractor vetting and background check.

<u>PAYMENT TERMS</u>: Payments will be made after inspection and approval of work by SynergyNDS, City Building Official &/or Insurance Adjuster. Accurate invoices and required project documentation must be submitted to SynergyNDS for project audit prior to payment. \*Material Deposits &/or Advanced Payments require Contractor to complete online registration in the FMIT Managed Vendor Program (MVP). MVP has an annual \$49.99 Registration Fee to be part of the Contractor Direct Repair Program. Material Deposits &/or Advanced Payments will require a 2% Invoice Payment Discount.

<u>HOLD HARMLESS</u>: To the fullest extent permitted by law, the Contractor/Vendor shall indemnify, defend, and hold harmless SynergyNDS, Inc & TML, their officers, agents, employees, elected, and appointed officials, Insurance Representatives and volunteers from and against any and all claims, losses or liability, including attorney's fees, arising from injury or death to persons or damage to property occasioned by any act, omission,

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

or failure of the Contractor/Vendor and any of its officers, agents, employees, and volunteers in satisfying the terms required by this contract.

**RIGHT TO ACCEPT, REJECT AND WAIVE DEFECTS**: TML &/or Contracting Agent reserves the right to: reject all quotations; waive formalities, technical defects, and minor irregularities; accept the quotation (if any) deemed most advantageous to and in the best interests of Insured Members of TMLIRP. Award will be based on price, contractor's daily performance capabilities, availability to provide the specified services when required &/or in accordance to critical path scheduling.

<u>DAMAGES</u>: Contractor will be held liable for any damage caused to the building and ancillary structure, and/or injury to the occupants resulting from the execution of the work or from not exercising proper precautionary protective measures. Any cost of repair/replacement resulting from damages shall be at the contractor's expense.

### **WORK-SITE PRACTICES:**

- Contractor's workers, as well as the various trade contractors entering or leaving the work area, will all attend a site-specific safety meeting as well as daily safety meetings prior the scheduled work day.
- Contractor's workers entering or leaving the work area will don or remove personal protective equipment and clothing in the staging area outside of each work area.
- Waste materials transported from the bag out unit must be moved in a fashion that prevents spreading contamination outside the work area.

**WORKER PERSONAL PROTECTION EQUIPMENT:** The National Institute for Occupational Safety and Health (NIOSH) provides the following interim guidelines and warnings to restoration workers.

- Steel toed leather boots should be worn. Tennis shoes or sneakers should *not* be worn because they will transfer contamination and will not prevent punctures, bites, or crush injuries.
- Goggles, safety glasses with side shields or full-face shields shall be used when performing restoration related activities that involve demolition, cutting or the use of ANY power tools. Sun/glare-protective lenses may be needed in some work settings. The use of goggles or protective eyewear should also be worn during the application of any cleaners, sanitizers or disinfectants.
- Soft hat or another protective head cover. Wear an American National Standards Institute (ANSI) rated hardhat if there is any danger of falling debris or electrical hazards.

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

- Hearing protection (when working in an environment with any noise that you must shout over to be heard).
- Comfortable, form fitting, light weight clothing including long pants and a long-sleeved shirt or coveralls. Additional PPE, respiratory protection, or clothing may be required when specific exposure hazards are identified or expected at the work site. In some instances, the protective ensemble components (garment, boots and gloves) may need to be impervious to contaminated flood or other site-specific chemical, physical, or biological hazards. In all instances, workers are advised to wash their hands with soap and clean water, especially before eating or drinking. Protect any cuts or abrasions with waterproof gloves and dressings. The use of insect repellant, sun block and lip balm may also be required for some work environments. Drink plenty of bottled water and take frequent rest breaks to avoid overexertion.

THERMAL STRESSES: HEAT: Workers are at serious risk for developing heat stress. Excessive exposure to hot environments can cause a variety of heat-related problems, including heat stroke, heat exhaustion, heat cramps, and fainting. To reduce the potential for heat stress, drink a glass of fluid every 15 to 20 minutes and wear loose- fitting clothing. Additionally, incorporate work-rest cycles into work routines and when possible distribute the workload evenly throughout the day.

\*\*\*\*Temporary cooling to the work areas shall only be authorized by the owner's representative based on the actual need for the work being performed. Where the conditions allow for the operation of part or all of the ventilation systems serving the work area then the need for temporary cooling is NOT necessary. The work area should be maintained at conditions that meet OSHA requirements for health and safety.\*\*\*

**WORKING IN CONFINED SPACES:** If you are required to work in a boiler, furnace, pipeline, pit, pumping station, septic tank, sewage digester, storage tank, utility vault, well, or similar enclosure, you should be aware of the hazards of working in confined spaces. A confined space has one or more of the following characteristics:

- limited openings for entry or exit;
- unfavorable natural ventilation; or
- Is not designed for continuous worker occupancy.

Toxic gases, a lack of oxygen, or explosive conditions may exist in the confined area, resulting in a potentially deadly atmosphere. Because many toxic gases and vapors cannot be seen or smelled, never trust your senses to determine if safe entry is possible. **Never** enter a confined space unless you have been properly trained, even

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

to rescue a fellow worker! If you need to enter a confined space and do not have the proper training and equipment, contact your local fire department for assistance.

<u>CONTRACT IMPLEMENTATION:</u> Contract will be awarded upon review of all bids and proposals received by SynergyNDS. Initiation of contract is engaged upon written bid award letter. At such time, Contractor signed Request for Service Pricing (RFP) will serve as Contract. Complete Contract engagement will occur upon SynergyNDS receipt of all required documentation including but not limited to:

- Bonding if Required (Performance Bond &/or Payment Bond)
- Certificate of General Liability Insurance
- Certificate of Auto Insurance
- Certificate of Worker's Compensation or Letter of Exemption
- Contractor's W-9
- State Licenses

Further description of insurance requirements is listed in "Insurance & Licensing Requirements."

**ASSIGNMENT OF CONTRACT**: Contractor shall not assign the contract or any part thereof to any person, firm, corporation or company unless such assignment is approved in writing by the Purchasing Agent. Such acceptance shall be at the sole discretion of the SynergyNDS upon request of the Contractor. Upon approved and executed written authorization, Contractor will be responsible for coordination of work with other trades. Failure to coordinate this work shall not constitute additional cost as governed by the Lump Sum Contract Award.

**ASSIGNMENT OF CONTRACTOR:** Contractor is responsible for supplying all required Personal Protective Equipment (PPE), including but not limited to the furnishing and appropriate use of: hard hat(s), safety glasses, face shields, ear plugs, gloves, boots, fall protection (where required), breathing protection (where required), tie off ropes/apparatuses/points (where required), fire extinguishers, first aid kits, etc. Contractor is required to be familiar with and follow all OSHA and State of Florida's safety requirements.

Contractor is to hold daily jobsite safety meetings that review the work to be performed, the hazards involved and the methods for reducing and eliminating such hazards, as well as maintain meeting records, - including attendance lists, which shall be kept onsite and available for SynergyNDS review at all times. Contractor shall be solely liable for any and all OSHA violations associated with his/her employees.

SynergyNDS reserves the right to hold weekly progress meetings for which the Subcontractor shall attend. Contractor shall be responsible for daily cleanup of the work performed herein. Failure to cleanup daily after trade will result in cleanup supplementation at Contractor's cost. Twenty-Four (24) hour notice will be given prior to supplementation. Contractor shall be responsible for delivery, loading, unloading, storage, protection, etc. of all work provided herein.

PR104225: CHHA CASA GRANDE DEVELOPMENT

**ENERGY EFFICIENCY:** The Contractor shall comply with all mandatory standards and policies relating to energy efficiency which are contained in the energy conservation plan issued in compliance with the Energy Policy and Conservation Act (Pub.L. 94-163) for the State in which the work under this contract is performed.

PROCUREMENT OF RECOVERED MATERIALS: (a) In accordance with Section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act, the Contractor shall procure items designated in guidelines of the Environmental Protection Agency (EPA) at 40 CFR Part 247 that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition. The Contractor should procure items designated in the EPA Guidelines that contain the highest percentage of recovered materials practical unless the Contractor determines that such items: (1) are not reasonably available in a reasonable period of time; (2) fail to meet reasonable performance standards, which shall be determined on the basis of the guidelines of the National Institute of Standards and Technology; (3) are only available at un price.

**FAILURE TO COMPLY**: For failure to deliver in accordance with specifications, SynergyNDS may cancel the contract or any part thereof and purchase services on the open market, charging any additional cost to the Contractor. Contractor shall comply with all applicable state, federal and local codes, and pay all permits, licenses and certificates, and other fees as required by the work.

**INSURANCE & LICENSING REQUIREMENTS**: Before starting work, the Contractor will provide SynergyNDS proof of Worker's Compensation and Commercial and Public Liability Insurance. The Contractor must be licensed to do business in the State of Florida and SynergyNDS must be named as an additional insured on general liability insurance certificate.

Contractor will need to go to <a href="www.syngeryfmit.com">www.syngeryfmit.com</a> and complete the initial registration for the Managed Vendor Program (MVP). Contractor will be required to upload the following information (when applicable) prior to contract award and eligible material deposits.

- The Contractor will carry Worker's Compensation Insurance for all employees engaged in work at the site, in accordance with State or Territorial Worker's Compensation Laws.
- Commercial and Public Liability with bodily injury and property damage limits will be at a combined single limit of at least \$500,000 to protect the contractor and each subcontractor against claims for injury to or death of one or more persons.
- Automobile Liability on owned and non-owned motor vehicles used on the site(s), or in connection with the sites, for a combined single limit for bodily injury and property damages of not less than \$500,000.00 per occurrence.
- Builder's Work Insurance limit of at least \$5,000.00 per occurrence and \$10,000.00 aggregate.
- Professional Liability \$1,000,000 per occurrence (if applicable).

#### PR104225: CHHA CASA GRANDE DEVELOPMENT

Contractor will not allow insurance coverage to lapse and will provide Turnkey Recovery Project Manager with updated Certificates of Insurance as necessary. All policies must provide that at least thirty (30) days' notice of cancellation will be given to the FMIT Project Manager and the contractor.

#### The certificate holder(s) must be noted as:

Synergy NDS, Inc. 1400 Sarno Rd Melbourne, FL 32935

Additional MANAGED PROGRAM INFORMATION is available at <a href="www.synergynds.com">www.synergynds.com</a> in support of:

- FMIT TurnKey Recovery
- MVP (Managed Vendor Program)
- FastTrack (Contractor Upfront Payment & Load Program).

### PR104225: CCHA CASA GRANDE DEVELOPMENT

This DOES NOT represent a commitment to buy. Any ACTUAL order resulting from this solicitation will be confirmed by Contract Engagement.

### **CONTRACTOR SUBMITTAL FORM**

Company Name		
Address:		
City	State Zip	
Phone No	Email	
I, the undersigned, have read and u preceding the attached Contractor S	understood all applicable Terms & Condition Submittal Form.	ns as described in the IFB Packet
Company Contact	Title	
Signature:	Date:	
LUMP SUM P	PROPOSAL – SUBMITTAL DEAI	<b>DLINE 7-25-19</b>
Location #: CCHA C	asa Grande Development	\$
☐Required   ☐Requested   Material Deposit		\$
	nced Payments require Contractor to complete online nnual \$49.99 Registration Fee to be part of the Contra	

### **RETURN BID TO:**

SynergyNDS

Email: bids@synergynds.com

Include Email Subject Line Reference: PR10422-CCHA-Casa Grande

Deposits &/or Advanced Payments will require a 2% Invoice Payment Discount.

### **CCHA CASA GRANDE – UNIT EXAMPLE**





Single Family Homes are located around two cul-de-sacs (Flores Ave & Troywood Cir)



### CCHA CASA GRANDE - FLOOD LOSS DEDUCTIBLE CALCULATIONS

UNIT	STREET	BDRM & BATH	FLOOR PLAN	FINISHED EST SF	DEMO PLAN
107	Troywood Circle	3 Bdrm	А	1200	4' Flood Cut
108	Troywood Circle	4 Bdrm	D	1350	4' Flood Cut
109	Troywood Circle	4 Bdrm	С	1300	4' Flood Cut
110	Troywood Circle	3 Bdrm - H	E	1200	4' Flood Cut
111	Troywood Circle	3 Bdrm	В	1150	4' Flood Cut
112	Troywood Circle	3 Bdrm	В	1150	4' Flood Cut
113	Troywood Circle	3 Bdrm - H	Е	1200	4' Flood Cut
114	Troywood Circle	3 Bdrm	Α	1200	4' Flood Cut
115	Troywood Circle	3 Bdrm	В	1150	4' Flood Cut
116	Troywood Circle	3 Bdrm	В	1150	4' Flood Cut
117	Troywood Circle	3 Bdrm	Α	1200	4' Flood Cut
118	Troywood Circle	3 Bdrm - H	Е	1200	4' Flood Cut
119	Troywood Circle	3 Bdrm	В	1150	4' Flood Cut
120	Troywood Circle	4 Bdrm	С	1300	4' Flood Cut
122	Troywood Circle	3 Bdrm	В	1150	NA
124	Troywood Circle	3 Bdrm	Α	1200	4' Flood Cut
4406	Wood Ave	4 Bdrm	D	1350	NA
4410	Wood Ave	2 Bdrm	G	900	4' Flood Cut
4414	Wood Ave	3 Bdrm	Α	1200	4' Flood Cut
110	Flores Ave	2 Bdrm	В	900	4' Flood Cut
112	Flores Ave	3 Bdrm	Α	1200	4' Flood Cut
114	Flores Ave	3 Bdrm - H	Е	1200	4' Flood Cut
115	Flores Ave	3 Bdrm	Α	1200	4' Flood Cut
116	Flores Ave	4 Bdrm	D	1350	4' Flood Cut
117	Flores Ave	2 Bdrm	F	900	4' Flood Cut
200	Flores Ave	2 Bdrm	F	900	4' Flood Cut
201	Flores Ave	3 Bdrm	В	1150	4' Flood Cut
202	Flores Ave	3 Bdrm - H	E	1200	4' Flood Cut
204	Flores Ave	3 Bdrm	В	1150	4' Flood Cut
206	Flores Ave	3 Bdrm	А	1200	4' Flood Cut
208	Flores Ave	2 Bdrm	F	900	4' Flood Cut
TOTAL ESTIMATED SE @ 33 450 SE					


**29 FLOOD DAMAGED UNITS** Estimated Total SF @ 33,450 SF Estimated Avg Unit @ 1,153 SF

TOTAL ESTIMATED SF @ 33,450 SF

CASA GRANDO I

11-2-02-21 m.q 92:42:40

CAIVIEKUN CO. HOUSING




12-20-2011


.m.q 05:22:40

CAMERON CO. HOUSING

--19562334590



FLOOR PLAN - UNIT 'C'



FLOOR PLAN - UNIT 'D'